# **Addendum No. 1 to the Tender Document**

## SUPPLY OF DIESEL TO MBS GENERATORS AND RENDERING OF ALLIED SERVICES





### PUNJAB METROBUS AUTHORITY

5<sup>th</sup> floor, Arfa Software Technology Park 346-B, Ferozepur Road, Lahore, Pakistan Phone: 042 - 99232540 URL: <u>www.punjab.gov.pk</u>

## Addendum No. 1 to the Tender Document

Due to some clarifications required in the RFP document, the following addendum is hereby issued; which shall form part and parcel of the original document titled:

"Supply of Diesel to MBS Generators and rendering of allied services", issued and uploaded on April 23, 2013. The contents of this addendum shall supersede/replace Clause 5.17, 5.18, 5.19, 25.2.5 and 25.2.6 of the original RFP document, and shall be read as part of the RFP document on the following websites:

Punjab Procurement Regulatory Authority : www.ppra.punjab.gov.pk

Punjab Portal : www.punjab.gov.pk

### ADDENDUM TO CLAUSE NO. 5.17, 5.18 and 5.19 OF THE RFP ISSUED ON April 23, 2013

- 5.17. Make available two Tank Lorries of sufficient <u>storage</u> capacity to smoothly undertake and perform the scope of work. The tank Lorries must be in good working condition and be equipped with sealed digital dispensing units <u>and a power supply/source (e.g. generator) to effectively carry out the decanting process including providing power to the flow-meter to be installed with the Auxiliary fuel tank of the generator.</u> The Service Provider shall be responsible for the prompt removal of vehicles broken down inside the MBS corridor.
- 5.18. Install (within 14 days of the award of contract), and replace *immediately* when its condition so warrants, high quality, *digital*, branded, sealed, flow-meter on *Auxiliary* fuel tank available with each generator. The flow-meters shall be used to monitor the quantity decanted into the *Auxiliary tank at each delivery*; therefore, the flow-meters must be of such quality/specifications that their readings, after calibration, should match those displayed by the dispensing unit attached on the delivery vehicle. The requirements for calibration of flow-meters and dispensing unit are provided in clause 5.19 below.
- 5.19. In order to ensure accurate readings of decanted fuel <u>quantity</u>, the Service Provider shall ensure timely calibration of both the dispensing units installed on the delivery vehicles, and the flow-meters installed on the fuel tanks, through a recognized agency/firm, as approved by the Client. At the minimum, the calibration shall be conducted on a quarterly basis or earlier as may be needed. The calibration reports shall be submitted to the Client within one week of the end of the quarter. Under no circumstances shall the flow-meters be removed / replaced without prior approval of the PMA.

### ADDENDUM TO CLAUSE NO. 25.2.5 and 25.2.6, OF THE RFP ISSUED ON April 23, 2013

#### 25.2. The Tender shall be rejected if any of the following occurs:

- 25.2.1. It is substantially non-responsive
- 25.2.2. It is submitted in other than prescribed forms, documents / by other than specified mode
- 25.2.3. It is incomplete, un-sealed, un-signed, hand written, partial, conditional, alternative, or late
- 25.2.4. It is subjected to interlineations / cuttings / corrections / erasures / overwriting

<mark>25.2.5. <u>(</u>deleted)</mark>

<mark>25.2.6. <u>(deleted)</u></mark>

- 25.2.7. The Bidder refuses to accept the corrected Total Tender Price
- 25.2.8. The Bidder has a conflict of interest with the procurer